

AD-A156 434


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAM  
DEERING RESERVOIR DAM (U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV NOV 78

1/1


UNCLASSIFIED

F/G 13/13

NL







MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A156 434

MERRIMACK RIVER BASIN  
DEERING , NEW HAMPSHIRE

## DEERING RESERVOIR DAM

NH 00282

NHWRB NO. 62.05

### PHASE I INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM



DTIC  
ELECTE  
JUL 09 1985  
S D  
G

DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

NOVEMBER 1978

DTIC FILE COPY

STATEMENT A  
Approved for public release  
Distribution Unlimited

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00282	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Deering Reservoir Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE November 1978
		13. NUMBER OF PAGES 76
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Merrimack River Basin Deering, New Hampshire Piscataquog River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is a 625 ft. long, 25 ft. high earth embankment dam. The inspection did not disclose any findings that indicate an immediate unsafe condition. The condition of the dam is good. The inspection revealed a right training wall which is badly cracked and in need of repair. Because the dam can pass 95% of the test flood without being overtopped, the spillway capacity is not considered to be seriously inadequate.		

DEERING RESERVOIR DAM

NH 00282

NHWRB 62.05

MERRIMACK RIVER BASIN  
DEERING, NEW HAMPSHIRE

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input checked="" type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/1	23/58

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

LETTER OF TRANSMITTAL  
FROM THE CORPS OF ENGINEERS TO THE STATE  
TO BE SUPPLIED BY THE CORPS OF ENGINEERS



NATIONAL DAM INSPECTION PROGRAM  
PHASE I - INSPECTION REPORT  
BRIEF ASSESSMENT

Identification No.: 00282  
Name of Dam: Deering Reservoir Dam  
Town: Deering  
County and State: Hillsboro, New Hampshire  
Stream: Piscataquog River  
Date of Inspection: August 15, 1978


Deering Reservoir Dam is a 625 foot long, 25 foot high earth embankment dam. A set of plans dated 1940 showing plan, elevation, typical sections and details as well as a set of construction specifications were available for this investigation. No construction data or design calculations were available.

The visual examination did not disclose any findings that indicate an immediate unsafe condition. The general condition of the dam is good. The inspection revealed a right training wall which is badly cracked and in need of repair, some surface erosion of the downstream face, inability to drain the reservoir due to blockage at the outlet structure and obstructions in the downstream channel.

Deering Reservoir Dam's spillway will not pass the required test flood. The dam's spillway capacity is approximately 95 percent of the test flood and consequently, the dam would be overtopped by approximately 0.15 feet under the test flood conditions. However, because the dam can pass 95 percent of the test flood without being overtopped, the spillway capacity is not considered to be seriously inadequate.

It is recommended that the owner engage a qualified engineer to design for the necessary repair of the badly cracked right training wall of the spillway and to evaluate further the potential for overtopping and the inadequacy of the spillway. It is also recommended that the owner repair and seed all surface erosion on the downstream face of the dam and provide for the removal of the fill placed in the river bed at the outlet structure.

The recommendations and remedial measures are described in Section 7 and should be addressed within two years after receipt of this Phase I - Inspection Report by the owner.



*Gordon H. Slaney, Jr.*

Gordon H. Slaney, Jr., P.E.  
Project Engineer

Howard, Needles, Tammen & Bergendoff  
Boston, Massachusetts



DEERING RESERVOIR DAM - Overview looking upstream

This Phase I Inspection Report on \_\_\_\_\_ Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

\_\_\_\_\_  
CHARLES G. TIERSCH, Chairman  
Chief, Foundation and Materials Branch  
Engineering Division

\_\_\_\_\_  
FRED J. RAVENS, Jr., Member  
Chief, Design Branch  
Engineering Division

\_\_\_\_\_  
SAUL COOPER, Member  
Chief, Water Control Branch  
Engineering Division

APPROVAL RECOMMENDED:

\_\_\_\_\_  
JOE B. FRYAR  
Chief, Engineering Division

\_\_\_\_\_  
THIS SHEET TO BE FURNISHED BY THE CORPS OF ENGINEERS

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	ii-iv
Overview Photo	v
Location Map	vi

## REPORT

1. PROJECT INFORMATION	1-1
1.1 General	1-1
a. Authority	1-1
b. Purpose of Inspection	1-1
1.2 Description of Project	1-1
a. Location	1-1
b. Description of Dam and Appurtenances	1-2
c. Size Classification	1-2
d. Hazard Classification	1-2
e. Ownership	1-2
f. Operator	1-2
g. Purpose of Dam	1-2
h. Design and Construction History	1-2
i. Normal Operational Procedure	1-3
1.3 Pertinent Data	1-3
2. ENGINEERING DATA	2-1
2.1 Design Data	2-1
2.2 Construction Data	2-1
2.3 Operation Data	2-1
2.4 Evaluation of Data	2-1

<u>Section</u>	<u>Page</u>
3. VISUAL INSPECTION	3-1
3.1 Findings	3-1
a. General	3-1
b. Dam	3-1
c. Appurtenant Structures	3-2
d. Reservoir Area	3-3
e. Downstream Channel	3-3
3.2 Evaluation	3-3
4. OPERATIONAL PROCEDURES	4-1
4.1 Procedures	4-1
4.2 Maintenance of Dam	4-1
4.3 Maintenance of Operating Facilities	4-1
4.4 Description of any Warning System in Effect	4-1
4.5 Evaluation	4-2
5. HYDRAULIC/HYDROLOGIC	5-1
5.1 Evaluation of Features	5-1
a. Design Data	5-1
b. Experience Data	5-1
c. Visual Observation	5-1
d. Overtopping Potential	5-1
e. Dam Failure Analysis	5-1
6. STRUCTURAL STABILITY	6-1
6.1 Evaluation of Structural Stability	6-1
a. Visual Observation	6-1
b. Design and Construction Data	6-1
c. Operating Records	6-1
d. Post-Construction Changes	6-1
e. Seismic Stability	6-1

Section

7. ASSESSMENT, RECOMM

7.1 Dam Assessmen

- a. Condition
- b. Adequacy
- c. Urgency
- d. Need for

7.2 Recommendation

7.3 Remedial Meas

7.4 Alternatives

APPENDIX A - INSPECTIO

APPENDIX B - ENGINEERI


APPENDIX C - PHOTOGRAPH

APPENDIX D - HYDROLOGI

APPENDIX E - INFORMATI  
INVENTORY



	<u>Page</u>
REMEDIAL MEASURES	7-1
	7-1
on	7-1
Investigation	7-1
	7-1
	7-2
	7-2
	A-1
	B-1
	C-1
LIC COMPUTATIONS	D-1
NED IN THE NATIONAL	E-1



NATIONAL DAM INSPECTION PROGRAM  
PHASE I INSPECTION REPORT  
DEERING RESERVOIR DAM

SECTION 1  
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Howard, Needles, Tammen & Bergendoff has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed were issued to Howard, Needles, Tammen & Bergendoff under a letter of July 12, 1978 from John P. Chandler, Colonel, Corps of Engineers. Contract No. DACW33-78-C-0356 has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. Deering Reservoir Dam is located in the Town of Deering, New Hampshire. Deering Reservoir forms the headwaters of the Piscataquog River. The Piscataquog River flows in a generally easterly direction for a distance of approximately 25 miles to its confluence with the Merrimack River in Manchester, New Hampshire. The dam is shown on U.S. G.S. Quadrangle, Hillsboro, New Hampshire, with coordinates approximately at N 43°03'10", W 71°50'40", Hillsboro County, New Hampshire. Deering Reservoir Dam's location is shown on the Location Map immediately preceding this page.

b. Description of Dam and Appurtenances. Deering Reservoir Dam is an earthfill structure approximately 25 feet high and 625 feet long from the right abutment to the spillway structure. The upstream face has a slope of approximately  $2\frac{1}{2}$  feet vertical to 1 foot horizontal ( $2\frac{1}{2}$ :1) with 1.5 foot riprap placed to within 2 feet of the dam crest. The downstream face has approximately a 2:1 slope for the first 5 feet from the top and approximately a  $2\frac{1}{2}$ :1 slope below this point to the toe of the dam. The appurtenant works consist of a concrete spillway, spillway channel and outlet works consisting of sluiceway with stoplogs and a reinforced concrete drain pipe. The sluiceway and spillway are located at the left abutment of the dam. The outlet works gate and conduit are located in the original Piscataquog River bed. Figure 1, located in Appendix B, shows the plan of the dam, spillway and outlet works. Photographs of each structure are shown in Appendix C.

c. Size Classification. Intermediate (hydraulic height - 21 feet, storage - 4,985 acre-feet) based on storage ( $\geq 1,000$  to 50,000 acre-feet) as given in the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. The dam's potential for damage rates it as a significant hazard classification. A major breach could result in the loss of a few lives, damage to the roadway immediately downstream and damage to approximately four houses.

e. Ownership. The present dam is believed to have been constructed in 1940 by the State of New Hampshire Water Resources Board and has been owned by the Water Resources Board since that time.

f. Operator. This dam is maintained and operated by the State of New Hampshire Water Resources Board, 37 Pleasant Street, Concord, New Hampshire 03301. Chairman of the Water Resources Board is Mr. George M. McGee, Sr.; Mr. Vernon Knowlton is Chief Engineer. Telephone No. (603)271-1110.

g. Purpose of Dam. The purpose of this dam is primarily to form a recreational pool with some flood control benefits which are described in Section 4, Operational Procedures.

h. Design and Construction History. The drawings for this dam were prepared by the New Hampshire Water Resources Board and are dated 1940. Construction was started and completed in that general time period. (Original dam owned by the New Hampshire Public Service Company had been destroyed during 1938 storm). The drawings and the specifications for this dam are available at the New Hampshire Water Resources Board. No in-depth design or construction data were disclosed for this dam.

i. Normal Operational Procedure. The Deering Reservoir Dam is used primarily for the retention of Deering Reservoir which is used for recreational purposes. A secondary purpose of the dam and its resulting reservoir area is for control of winter and early spring runoff. The normal operational procedure for this dam is to remove the stop logs in the sluiceway sometime in the month of October or November of each year thus lowering the reservoir level approximately 5 feet below the dam's spillway elevation. The resultant available storage is used to control snow melt and heavy runoff during the winter and spring months. In May of each year, the stop logs are then reinserted into the sluiceway to at least the elevation of the spillway, thus returning the reservoir level to spillway level for summertime recreational purposes.

### 1.3 Pertinent Data

a. Drainage Area. The drainage area above the Deering Reservoir Dam consists of approximately 4.5 square miles of rolling, heavily wooded hills. The periphery of Deering Reservoir is comprised of wooded area with some residences located near the reservoir.

The reservoir area itself contains some small islands but is devoid of dead trees protruding through the surface or other visible impediments to navigation. There are some private docks or piers noted along the area inspected.

The watershed supporting Deering Reservoir is forested rolling terrain with very few flat areas. All areas in the basin are well vegetated with a few paved roads and housing. Topographic elevation in the watershed ranges from about 1,520 to 920 feet MSL.

There are several relatively small tributaries which drain into the reservoir. The longest of these tributaries is approximately 1.5 miles long with a vertical drop over its length of over 300 feet.

### b. Discharge at Dam Site

(1) The outlet works for the Deering Reservoir Dam consists of a 5 foot wide sluiceway and a 24 inch diameter outlet drain pipe. The reservoir behind the dam can be lowered 5 feet below the spillway crest elevation (921) by the removal of the wooden stop logs in the sluiceway. The 24 inch outlet drain pipe was designed to allow dewatering of the reservoir from the bottom of the sluiceway elevation (916) to the original river bed elevation (902).

(2) The maximum discharge at this dam site is unknown.

(3) The spillway capacity with a water surface at the top of the dam and assuming stop logs in sluiceway set at the same elevation as the permanent spillway crest is approximately 4,600 cfs at an elevation of 927.0.

(4) The spillway capacity with the water surface at the test flood elevation, again assuming the stop logs in the sluiceway are set at the same elevation as the permanent spillway crest is approximately 4,760 cfs at an elevation of approximately 927.15.

(5) The stoplog sluiceway capacity at normal pool elevation (921.0) is estimated to be 150 cfs upon removal of all stoplogs.

(6) The total spillway capacity at the test flood elevation of 927.15 is estimated to be 4,760 cfs.

(7) The total project discharge at the test flood elevation of 927.15 is estimated to be 4,860 cfs.

c. Elevation (feet above MSL) based on elevation of 921.0 shown on U.S.G.S. quad sheet assumed to be pool elevation at permanent spillway crest.

(1) Streambed at centerline of dam - 902.0<sub>+</sub>.

(2) Maximum tailwater - unknown.

(3) Upstream portal invert diversion tunnel - none.

(4) Recreation pool - 922.0.

(5) Full flood control pool (see Section 1.2.i) - 916.0.

(6) Spillway crest (permanent spillway) - 921.0.

(7) Design surcharge - unknown.

(8) Top dam - 927.0.

(9) Test flood surcharge - 927.15.

d. Reservoir (miles)

(1) Length of Maximum pool - 1.5.

(2) Length of Recreational pool - 1.5.

(3) Length of flood control pool - 1.2 $\pm$ .

e. Storage (acre-feet)

(1) Recreation pool - 3,400.

(2) Flood control pool (see Section 1.2.i)

(3) Spillway flood pool (at permanent spillway crest) - 3,100.

(4) Top of dam - 4,980.

(5) Test flood pool - 5,027.

f. Reservoir Surface (acres)

(1) Recreation pool - 314 $\pm$ .

(2) Flood control pool -  $\approx$ 314. Note: Surface areas used for these were same as at spillway crest.

(3) Spillway crest - 314.

(4) Test flood pool -

(5) Top dam -

g. Dam

(1) Type - earthen dam with concrete spillway.

(2) Length - 650 $\pm$  feet, overall..

(3) Height - 25 feet (maximum).

(4) Top width - 10 feet.

(5) Side slope - US = 2 $\frac{1}{2}$ :1; DS = 2:1 and 2 $\frac{1}{2}$ :1.

(6) Zoning - unknown.

(7) Impervious core - compacted earth (by specifications).

(8) Cutoff - concrete at sluiceway.

(9) Grout curtain - none.

(10) Other - none.

h. Diversion and Regulating Tunnel

See Section j below.

i. Spillway

- (1) Type - concrete, curved with straight drop.
- (2) Length of weir - 78.5 feet.
- (3) Crest elevation - 921.0.
- (4) Gates - stoplog sluiceway - 5 feet wide.
- (5) U/S channel - none.
- (6) Downstream channel - a 90 foot reach approximately 40 feet wide downstream of the spillway leads to a roadway bridge, again 40 feet wide. Below the bridge the downstream channel continues approximately 200 feet to the natural channel with overhanging trees.

j. Regulating Outlets. Regulating outlet consists of a 24 inch diameter reinforced concrete drain pipe at elevation 905.75 which was designed to discharge into the river bed directly below the dam. The pipe inlet is controlled by a manually operated wooden slide gate. The outlet to this drain conduit is buried, and complete discharge of the reservoir is not possible under present conditions.

## SECTION 2 ENGINEERING DATA

### 2.1 Design

A set of plans dated 1940 showing plan, elevation, typical sections and details along with a set of specifications are available at the State of New Hampshire Water Resources Board. No in-depth engineering calculations were found. A description of repairs which included the removal and replacement of 29 feet of the right abutment wall was also available. This data was dated 1963.

### 2.2 Construction

No construction records are available for use in evaluating the dam.

### 2.3 Operation

No engineering operational data were disclosed.

### 2.4 Evaluation

a. Availability. The Deering Reservoir Dam was designed by the New Hampshire Water Resources Board. Other than the plans and specifications described above, no additional engineering data was found to be available.

b. Adequacy. Available engineering data and drawings are considered adequate for a Phase I investigation.

c. Validity. The field investigation indicated that the external features of the Deering Reservoir Dam substantially agree with those shown on the furnished plans.



SECTION 3  
VISUAL INSPECTION

3.1 Findings

a. General. The field inspection of Deering Reservoir Dam was made on August 15, 1978. The inspection team consisted of personnel from Howard, Needles, Tammen & Bergendoff and Geotechnical Engineers, Inc. A representative of the State of New Hampshire, Water Resources Board was also present during portions of the inspection. Inspection checklists, completed during the visual inspection are included in Appendix A. At the time of the inspection, the water level was approximately 2½ inches above the permanent spillway elevation, being approximately 7½ inches below the flashboard elevation. Water was passing over the spillway approximately ½ inch deep. The upstream face of the dam could only be inspected above this water level.

b. Dam. Visual inspection of the embankment indicated no signs of distress. Since completion of the present dam, debris has been dumped in the old river channel downstream of the dam and roadway at the toe of the dam. This debris has buried the outlet works of the 24-inch-diameter conduit. This filling of the river channel was reported to the Board of Selectmen of Deering by the New Hampshire Water Resources Board in 1965.

Upstream Slope

Only the upper 6 ft. of the upstream slope was visible at the time of inspection. Photos 3 and 4 show the slope, which is in good condition. In some areas excessive vegetation has grown in the riprap. Personnel from New Hampshire Water Resources Board were spraying to eradicate the vegetation the day of the dam inspection.

Crest

The crest of the dam has no pavement. No evidence of cracking or misalignment was observed.

Downstream Slope

The face of the entire downstream slope was traversed along two lines: (1) along the crest and (2) along the toe. In addition, the central section of the dam between Stations 4+00 and 6+50 was traversed at intermediate elevations.

The slope is in generally good condition. In some areas the turf and grass cover is not as dense as it should be, and there is some minor erosion of the slope due to trespassing on the slopes. This erosion can be seen in Photos 5 and 6. Near the right abutment there is an area of dense undergrowth and trees. In general, the trees are below the dam slope. Personnel from the New Hampshire Water Resources Board indicated that they had planned to clean this area of excessive growth.

No seepage or damp areas were observed along the toe of the dam.

c. Appurtenant Structures. Visual inspection of the spillway structure showed the concrete surface and the two construction joints to be in generally good condition. There is, however, some erosion of the concrete joints. Photo 9 shows the general view of the spillway structure, with details of joint deterioration being shown on Photo 11.

The right training wall of the spillway is badly cracked. The extent of the cracking can be seen in Photos 10, 11, 12 and 13. Construction plans indicate that the gravity training walls were built without reinforcing steel. Deteriorated concrete as disclosed by visual inspection, i.e. deep cracks and spalling, will be exposed to rapid deterioration which could eventually lead to the possible collapse of this wall. The integrity of this wall is important to the embankment for the following reasons:

1. Collapse of this wall would likely be followed by collapse of the fill immediately behind the wall, resulting in a shortened seepage path through and beneath the dam.
2. If collapse were to take place during periods of high flow, erosion would take place at the toe of the dam.

The wet area on the right training wall (Photo 12) at the wall and footing-stem intersection is believed to be from surface drainage. However, this cracked wall section is adjacent to the downstream side of the dam embankment and should be repaired.

The outlet works for Deering Reservoir, consisting of gate, 24 inch conduit and outlet headwall were not inspected as the gate structure was well below the water surface and the outlet headwall was buried by debris. The outlet works discharge

channel, located in the original river bed, has been filled in with what appears to be roadway waste material, boulders and tree stumps. This fill material extends approximately 90 feet downstream of the outlet structure. Photos 15 and 16 show the results of this filling in of the river channel.

Visual inspection of the spillway discharge channel showed it to be in generally good condition. Bed rock in the channel is in good condition with no evidence of loose rock. There are no overhanging trees that would appear to obstruct free flow of the channel discharge.

d. Reservoir Area. The reservoir slopes are generally covered with trees and brush. Cottages are scattered along the shoreline. The amount of siltation within the reservoir is unknown.

e. Downstream Channel. The downstream channel has a gravel bottom covered with many rocks and is heavily lined with trees, many overhanging the channel. There is one cottage immediately downstream on the right side. The channel leads to a large swampy area approximately 6000 feet downstream. Photos 17 and 18 show the general downstream conditions.

### 3.2 Evaluation

Visual examination indicates no immediate safety problem. The condition of the dam is generally good, however, the right training wall is badly cracked, and collapse of a portion of this wall would expose the embankment to sliding and erosion. This wall must be repaired. The inspection also revealed the following:

- (a) Inability to drain the reservoir due to the filling of the river channel at the outlet works of the 24 inch diameter conduit.
- (b) Minor erosion of the downstream face.
- (c) Many overhanging trees on the downstream channel.

## SECTION 4 OPERATIONAL PROCEDURES

### 4.1 Procedure

The Deering Reservoir Dam is used primarily for the retention of Deering Reservoir which is used for recreational purposes. A secondary purpose of the dam and its resulting reservoir area is for control of winter and early spring runoff. The normal operational procedure for this dam is to remove the stop logs in the sluiceway sometime in the month of October or November of each year thus lowering the reservoir level approximately        feet below the dam's spillway elevation. The resultant available storage is used to control snow melt and heavy runoff during the winter and spring months. In May of each year, the stop logs are then reinserted into the sluiceway to at least the elevation of the spillway, thus returning the reservoir level to spillway level for summertime recreational purposes.

### 4.2 Maintenance of Dam

This dam is visited by one of the State of New Hampshire, Water Resources Board's dam operators approximately once per week. During these visits water levels are recorded, grass is cut as necessary, painting is done as necessary and any major deficiencies that may be noted are reported to the Water Resources Board. Occasional clearing of the brush on the embankment is also scheduled on a need basis.

During 1963, repairs were made to the dam which included the removing and replacing of approximately 29 feet of the cracked section of the abutment wall and stop log slab. A new 15 foot cutoff wall was also constructed upstream of the stop log section, and a gravel and storm drain was built downstream of this cutoff wall to drain water away from the abutment wall.

### 4.3 Maintenance of Operating Facilities

As the outlet works are either below water (at the inlet) or buried beneath fill (at the outlet) no maintenance is performed on these facilities.

### 4.4 Description of Warning Systems

There are no warning systems in effect at this facility.

#### 4.5 Evaluation

The current operation and maintenance procedures for Deering Reservoir Dam are inadequate to insure that all problems encountered can be remedied within a reasonable period of time. The owner should establish a written operation and maintenance procedure as well as establishing a warning system to follow in event of floodflow conditions or imminent dam failure.

## HYDROLOG

### 5.1 Evaluation of Fee

a. General. The dam approximately 25 feet right abutment to the works consist of an 78 stop log sluiceway section conduit. The dam is located on the Piscataquag River and primarily used for recreation reservoir level during the dam is also used to store and stormwater runoff. Reservoir Dam is classified as having a maximum storage

b. Design Data. were disclosed for Deering

c. Experience Data. present Deering Reservoir site (plans, description) during the storm of 1961 facility, maximum flood

d. Visual Observations. portion of the project time of the inspection

e. Overtopping Investigation. operational information was performed using data on watershed size and the Probable Maximum Flood curves issued by the Corps of Engineers for an area of 4.5 square miles flood inflow at Deering. Following the guidance of the Corps of Engineers Storage on Maximum Probable Flood discharge of 4,560 cfs the top of the dam is of the test flood discharge in the dam being over

f. Dam Failure. dam at maximum pool water

Guidance for Estimating Downstream Dam Failure Hydrographs issued by the Corps of Engineers. The analysis covered the reach extending from the dam to Weare Reservoir. Failure of Deering Reservoir Dam at maximum pool would probably result in a downstream channel depth of approximately 15.0 feet between the dam and the swampy area approximately 6,000 feet downstream. An increase in water depth of this magnitude would probably result in the loss of less than 10 lives, sever the road immediately downstream of the dam and might destroy one or two houses. This volume of water entering the swampy area would probably create a depth of about 10 feet. Between this swampy area and Weare Reservoir, one or two additional homes could possibly be damaged as well as the possibility of damage to two roadways.

SECTION 6  
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations. The visual inspection did not disclose any immediate stability problems with the embankment. However, the right training wall of the spillway is badly cracked, and collapse of this wall would endanger the integrity of the embankment.

b. Design and Construction Data. Design drawings and construction specifications exist and indicate that the embankment consists of two zones; a wide compacted impervious upstream zone protected by riprap and a compacted downstream pervious zone which incorporates a substantial rock toe. A one-foot-thick filter has been placed between the downstream zone and the rock toe. The upstream and downstream slopes are 1 vertical: 2 horizontal, flattening to 1 vertical: 2.5 horizontal at the normal pool elevation.

c. Operating Records. No operating records were made available.

d. Post-Construction Changes. In 1963, repairs were made to the existing dam consisting of removing and replacing approximately 29 feet of a cracked section of the right training wall and the stop log slab. A new 15 foot cutoff wall was also constructed upstream of the stop log section and a gravel and stone drain was built downstream of this cutoff wall to drain water away from the training wall.

Since construction of this dam in 1940 and prior to 1965, the Town of Deering, in an attempt to improve roadway conditions in the vicinity of the dam, hauled in stumps, boulders and gravel to widen the roadway section. This resulted in the outlet structure to the reservoir drain being blocked. Initially, this blockage extended approximately 18 feet downstream of the drain outlet. Since that time, it appears that this type of material has continued to be disposed of in the river bed such that the fill section presently extends about 90 feet beyond the drain outlet.

e. Seismic Stability. The dam is located in Seismic Zone 2, and in accordance with recommended Phase I guidelines does not warrant seismic analysis.



SECTION 7  
ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual examination did not disclose any findings that indicate an immediate unsafe condition. The condition of the dam is generally good. The inspection revealed the following:

(1) The right training wall is badly cracked and in need of repair.

(2) Inability to drain the reservoir because of blockage at the outlet structure.

(3) Some surface erosion of the downstream face is evident.

(4) Downstream channel obstruction caused by overhanging trees.

(5) Inadequacy of the spillway.

The hydraulic analysis reveals that the dam cannot pass the required test flood. However, as it can pass approximately 78 percent of the test flood without being overtopped, the spillway capacity is not considered seriously inadequate.

b. Adequacy of Information. The information made available by the New Hampshire Water Resources Board was totally adequate for a Phase I level of investigation.

c. Urgency. This dam is in generally good condition. The recommendation and remedial measures described in 7.2 and 7.3 should be implemented within two years after receipt of this Phase I Inspection Report by the owner.

d. Need of Additional Investigation. The findings of the visual inspection do not warrant additional investigation. However, repair of the spillway training wall should be undertaken, which work should include determining why the wall cracked and appropriate measures taken to prevent a similar concurrence to the repaired wall.

7.2 Recommendations

It is recommended that the owner engage a qualified engineer to design for the necessary repair of the badly

cracked right training wall of the spillway and to evaluate further the potential for overtopping and the inadequacy of the spillway.

### 7.3 Remedial Measures

(a) Repair and seed all surface erosion on the downstream face of the dam.

(b) Arrange to have the fill placed in the river bed removed.

(c) The tree and brush growth in the downstream channel should be removed and kept free in the future.

(d) Develop a written operational procedure to follow in the event of flood flow conditions or imminent dam failure.

(e) Continue the technical inspection program on a bi-annual basis.

### 7.4 Alternatives

There are no practical alternatives to the recommendations of Section 7.2 and 7.3 except that on an interim basis the owner may consider operating the reservoir at a lower level throughout the year so as to provide more storage for extreme flood events.

APPENDIX A

VISUAL CHECK LIST WITH COMMENTS

VISUAL INSPECTION CHECK LIST  
PARTY ORGANIZATION

PROJECT Deering Reservoir

DATE August 15, 1978

TIME 10 a.m.

WEATHER Sunny and Warm

W.S. ELEV. 921.1 U.S. 903<sup>+</sup> DN.S

PARTY:

- |                                     |           |
|-------------------------------------|-----------|
| 1. <u>Lyall Milligan N.H.W.R.B.</u> | 6. _____  |
| 2. <u>Gordon Slaney, HNTB</u>       | 7. _____  |
| 3. <u>Stan Mazur, HNTB</u>          | 8. _____  |
| 4. <u>D. P. LaGatta, GEI</u>        | 9. _____  |
| 5. _____                            | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Dam</u>	<u>Dan LaGatta</u>	
2. <u>Spillway, Sluiceway</u>	<u>Stan Mazur</u>	
3. <u>Outlet Works/Downstream Channel</u>	<u>Gordon Slaney</u>	
4. _____		
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		

# PERIODIC INSPECTION CHECK LIST

PROJECT Deering Reservoir

DATE August 15, 1978

PROJECT FEATURE Dam Embankment

NAME D. P. LaGatta

DISCIPLINE Geotechnical Eninegers Inc.

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	927.0
Current Pool Elevation	921.2
Maximum Impoundment to Date	Unknown.
Surface Cracks	None visible.
Pavement Condition	No pavement.
Movement or Settlement of Crest	None visible.
Lateral Movement	None visible.
Vertical Alignment	No misalignment observed.
Horizontal Alignment	
Condition at Abutment and at Concrete Structures	Right training wall of spillway badly cracked. See Section 3.1.c.
Indications of Movement of Structural Items on Slopes	None observed.
Trespassing on Slopes	There has been minor erosion on d.s. slope due to trespassing.
Sloughing or Erosion of Slopes or Abutments	
Rock Slope Protection - Riprap Failures	Riprap in good condition with minor growth which is removed yearly.
Unusual Movement or Cracking at or near Toes	
Unusual Embankment or Downstream Seepage	None observed.
Piping or Boils	None observed.
Foundation Drainage Features	Design dwgs. indicate rock toe drain.
Toe Drains	None visible.
Instrumentation System	None.



DATE August 15, 1978

NAME D. P. LaGatta

NAME G. Slaney

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	None.
a. Approach Channel	
Slope Conditions	
Bottom Conditions	
Rock Slides or Falls	
Log Boom	
Debris	
Condition of Concrete Lining	
Drains or Weep Holes	
b. Intake Structure	
Condition of Concrete	
Stop Logs and Slots	
	Intake structure below water surface and inaccessible for inspection.

# PERIODIC INSPECTION CHECK LIST

PROJECT Deering Reservoir

DATE August 15, 1978

PROJECT FEATURE Control Tower

NAME \_\_\_\_\_

DISCIPLINE Structural Engineer

NAME S. Mazur

## AREA EVALUATED

## CONDITION

### OUTLET WORKS - CONTROL TOWER

This facility has no tower.

#### a. Concrete and Structural

General Condition

Condition of Joints

Spalling

Visible Reinforcing

Rusting or Staining of Concrete

Any Seepage or Efflorescence

Joint Alignment

Unusual Seepage or Leaks in Gate Chamber

Cracks

Rusting or Corrosion of Steel

#### b. Mechanical and Electrical

Air Vents

Float Wells

Crane Hoist

Elevator

Hydraulic System

Service Gates

Emergency Gates

Lightning Protection System

Emergency Power System

Wiring and Lighting System

# PERIODIC INSPECTION CHECK LIST

PROJECT Deering Reservoir

DATE August 15, 1978

PROJECT FEATURE Conduit

NAME S. Mazur

DISCIPLINE Hydraulic Engineer/Structural Engineer

NAME G. Slaney

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u>	24 inch RCP drain conduit was inaccessible for inspection as intake was below water and outlet has been covered with borrow and waste material.
General Condition of Concrete	
Rust or Staining on Concrete	
Spalling	
Erosion or Cavitation	
Cracking	
Alignment of Monoliths	
Alignment of Joints	
Numbering of Monoliths	



# PERIODIC INSPECTION CHECK LIST

PROJECT Deering Reservoir

DATE August 15, 1978

PROJECT FEATURE Outlet Structure/Channel

NAME D. P. LaGatta

DISCIPLINE Geotechnical Engr./Hydraulic Engr.

NAME G. Slaney

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining</p> <p>Spalling</p> <p>Erosion or Cavitation</p> <p>Visible Reinforcing</p> <p>Any Seepage or Efflorescence</p> <p>Condition at Joints</p> <p>Drain Holes</p> <p>Channel</p> <p>Loose Rock or Trees Overhanging Channel</p> <p>Condition of Discharge Channel</p>	<p>Outlet structure not examined as it has been filled over with borrow and waste material during apparent roadway construction. Three sink holes were observed in the vicinity of outlet structure.</p> <p>Good.</p> <p>See text for discussion of dumped fill blocking conduit.</p>

# PERIODIC INSPECTION CHECK LIST

PROJECT Deering Reservoir

DATE August 15, 1978

PROJECT FEATURE Spillway/Discharge Channel

NAME D. P. LaGatta

DISCIPLINE Structural Engr./Geotechnical Engr.

NAME S. Mazur

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	
General Condition	Good.
Loose Rock Overhanging Channel	None.
Trees Overhanging Channel	None of significance.
Floor of Approach Channel	Good condition.
b. Weir and Training Walls	
General Condition of Concrete	Good - see text.
Rust or Staining	Some at drain holes.
Spalling	None.
Any Visible Reinforcing	None observed.
Any Seepage or Efflorescence	Seepage at bottom of right training wall about 25 feet downstream of spillway. Drainage beneath wall, see text, Section 3.
Drain Holes	
c. Discharge Channel	
General Channel	Good.
Loose Rock Overhanging Channel	No loose rock.
Trees Overhanging Channel	None.
Floor of Channel	Bedrock - good condition.
Other Obstructions	Bridge.

# PERIODIC INSPECTION CHECK LIST

PROJECT Deering Reservoir

DATE August 15, 1978

PROJECT FEATURE Service Bridge

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

## AREA EVALUATED

## CONDITION

### OUTLET WORKS - SERVICE BRIDGE

This facility has no service bridge.

#### a. Super Structure

Bearings

Anchor Bolts

Bridge Seat

Longitudinal Members

Under Side of Deck

Secondary Bracing

Deck

Drainage System

Railings

Expansion Joints

Paint

#### b. Abutment & Piers

General Condition of Concrete

Alignment of Abutment

Approach to Bridge

Condition of Seat & Backwall

f. Dam Failure  
dam at maximum pool w

- D**
1. LIST OF DESIGN, CO
  2. PAST INSPECTION RI
  3. PLANS AND DETAILS
- G I**

AVAILABLE ENGINEERING DATA


A set of plans dated 1940 showing plan, elevation, typical sections and details are available at the New Hampshire Water Resources Board, 37 Pleasant Street, Concord, New Hampshire 03301.

A set of construction specifications is also available at the New Hampshire Water Resources Board.

# DEERING RESERVOIR



LEGEND  
 1. ORIGINAL LOCATION WHERE PHOTO  
 WAS TAKEN AND INSPECTION



SECTION THROUGH SPILLWAY  
 PARALLEL TO SPILLWAY

## NOTES


1. THE ELEVATIONS SHOWN ARE BASED ON AN ELEVATION OF 1000 FEET. THE ELEVATIONS SHOWN ON THESE DAMS ARE BASED ON THE ELEVATION OF 1000 FEET. THE ELEVATIONS SHOWN ON THESE DAMS ARE BASED ON THE ELEVATION OF 1000 FEET.
2. THE ELEVATIONS SHOWN ON THESE DAMS ARE BASED ON THE ELEVATION OF 1000 FEET. THE ELEVATIONS SHOWN ON THESE DAMS ARE BASED ON THE ELEVATION OF 1000 FEET.

## DEERING DAM

DEERING DAM



SECTION OF DAM AT STA. 6+00



SECTION ON & OF CONDUIT

DEERING DAM

PAST INSPECTION REPORTS



MEMORANDUM

FROM: Francis C. Moore  
Civil Engineer

November 16, 1965

RE: Blocking of Pond Drain Outlet at Deering Reservoir

TO: Leonard R. Frost  
Water Resources Engineer

This morning I investigated the blocking of the outlet drain at Deering Reservoir. The town road agent apparently decided that the old river channel was a good place to dump large boulders, stumps, logs and earth to widen the inside of the curve in the road.

The blockage extends about eighteen feet downstream from the outlet at river channel elevation and about ten feet downstream at the top of slope. The channel is filled in parallel to the road with the top of slope moved about twenty feet further away from the road than originally constructed.

I left a pole with orange tape on it at the approximate location of the outlet of the pond drain.

As this blockage prevents any possible draining of Deering Reservoir under present conditions, I suggest that the Town of Deering (or those placing this fill) be required to uncover the outlet and provide an adequate channel from it. This will probably require a power shovel as there are boulders in the fill up to 2 cubic yards.

*Francis C. Moore*  
Francis C. Moore  
Civil Engineer

FCM/gam

APPENDIX C

PHOTOGRAPHS

FOR LOCATION OF PHOTOS, SEE FIGURE 1  
LOCATED IN APPENDIX B



Photo No. 1 - General view of reservoir from left abutment.



Photo No. 2 - General view of reservoir from center of dam.



Photo No. 3 - General view of dam from left abutment.



Photo No. 4 - General view of dam from right abutment.



Photo No. 5 - Erosion of downstream slope.



Photo No. 6 - Downstream slope showing erosion areas.




Photo No. 7 - General view of spillway structure, looking toward left abutment.



Photo No. 8 - Spillway structure and sluiceway structures, looking toward right abutment.




Photo No. 9 - Spillway structure joint detail.



Photo No. 10 - Sluiceway structure, conditions and details.



Photo No. 11 - Right training wall of sluiceway.



Photo No. 12 - Right training wall, deterioration of concrete (cracks, spalling and seepage).





Photo No. 13 - Right training wall, close up of expansion join.



Photo 14 - General view of spillway channel and roadway bridge.



Photo No. 15 - Sinkhole  
condensation  
in hole




Photo No. 16 - Downside  
downside



Photo No. 17 - General view of downstream channel.



Photo No. 18 - General view of downstream area.

APPENDIX D

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

VEEIKING DAM - DEERING, N.H.

BASIC DATA:

Drainage area = 4.5 square miles (N.H. Water Control Comm. data verified)

Based on Corps of Engineers guidelines:

SIZE CLASSIFICATION: INTERMEDIATE (storage  $\geq 1000$  and  $< 50,000$  ac-ft)HAZARD POTENTIAL CLASSIFICATION: SIGNIFICANT

For dams with an Intermediate size classification and Significant hazard potential a test flood equal to the PMP is indicated in the Corps guidelines.

ELEVATION VS. WATER SURFACE AREA VS. VOLUME

Conditions	Elevation* (ft.)	Surface area** (acres)	Reservoir volume (ac-ft.)
1. Crest of dam embankment	103.0	314	4984
2. Max. flood height based on N.H. Water Control Comm. data	100.0	314	4042
3. Top of flashboards	98.0	314	3414
4. Permanent spillway	97.0	314	3100
5. Normal drawdown (elev. of bot. of stoplog sluiceway)	92.4	250	1900
6. Maximum drawdown	84.0		
7. Original pond	81.0	100	

\* elevations in above table are referenced to local datum and are as provided in N.H. Water Control Commission data

\*\* surface area above permanent spillway was assumed to be same as the permanent spillway surface area of 314 acres as per contract modification of dam inspection guidelines.

Note: It is assumed that the normal pool elevation of 92.1 (as shown on the USGS quad sheet) is equal to the permanent spillway crest elevation of 97.0 (local datum).

## ICEEING DAM

### SPILLWAY DATA

Permanent spillway length : 78.5 ft.  
 Stoplog sluiceway (acts as spillway) : 5.0 ft.  
 Total effective length of spillway : 83.5 ft.

type: concrete wall  
 structural height: 5 feet ±

### DAM DATA

type: earth w/ impervious core  
 crest elev: 103.0 local datum  
 length: 650 ft.  
 highest depth of embankment: 25 ft.

### SPILLWAY CAPACITY DETERMINATION

To determine the spillway capacity it is assumed that flashboards along the permanent spillway will have washed away and the stoplog sluiceway will be set at elev. 97.0, the elevation of the permanent spillway.

Maximum elevation before dam overtopped = 103.0

Head =  $103.0 - 97.0 = 6.0$  ft. (max. before dam overtopped)

Since the height of the conc. spillway is so low, it is necessary to investigate downstream conditions to determine if the spillway will be submerged by a downstream tailwater. Look at normal depth ( $d_n$ ) for various flows in downstream channel.

## LEAKING DAM

### SPILLWAY CAPACITY DETERMINATION (cont.)

Channel data:


width = 40'

mannings' coef. = 0.03 (rock channel)

slope = 0.03 ft. / ft.

Compute  $d_n$  for the following flows in downstream channel

$Q$ (cfs)	$d_n$ (ft.)	remarks
2,000	3.05	
4,000	4.75	
6,000	6.20	spillway submerged
8,000	7.51	" "
10,000	8.75	" "



Submerged Weir

For submerged weir:

$$\frac{Q}{Q_1} = \left[ 1 - \left( \frac{H_2}{H_1} \right)^n \right]^{0.385}$$

reference: Std. Handbook for  
Civil Engineers, Merritt

where:  $Q$  = discharge for submerged conditions, cfs

$Q_1$  = free discharge cfs

$n$  = exponent in free discharge equation,  $Q_1 = CLH_1^{3/2}$

$C = (3.21 + 0.4 \frac{H_1}{P})$

$P$  = height of weir

for  $0.5 \leq \frac{H_1}{P} \leq 5$  (Rehbock's equation)

For DEERING DAM

SPILLWAY CAPACITY DETERMINATION (cont.)

To compute the maximum spillway capacity without overtopping the dam (elev. 103.0)  $H_1 = 103.0 - 97.0 = 6.0$  ft.

$$\text{then } Q = Q_1 \left[ 1 - \left( \frac{H_2}{H_1} \right)^{3/2} \right]^{0.385}$$

$$\text{or } Q = C L H_1^{3/2} \left[ 1 - \left( \frac{H_2}{H_1} \right)^{3/2} \right]^{0.385}$$

$H_2$  and  $Q$  are unknowns, therefore use trial & error procedure. 1st trial assume  $H_2 = 2.5$  ft. for  $H_1 = 6.0$  ft.

Trial No.	$H_1$ (feet)	$H_2$ (feet) "Assumed"	$Q$ (cfs)	$d_n$ , normal depth (feet)	$H_2$ (assumed) vs. $H_2$ (computed)	Status
1	6.0	2.5	4080	4.82	2.5 $\neq$ 0	N.G.
2	6.0	0.0	4602	5.21	0 $\neq$ .21	N.G.
3	6.0	0.2	4591	5.20	0.2 = 0.2	<u>O.K.</u>

therefore based on above trial & error process the maximum spillway capacity = 4591 cfs (say 4600 cfs)

this flow creates a downstream flow depth  $d_n$  of 5.2 ft. which submerges the spillway by 0.2 ft.

Maximum spillway capacity before dam overtopped  $\approx 4600$  cfs

EFFECT OF SURCHARGE STORAGE ON MAX. PROBABLE DISCHARGE

Drainage area = 4.5 sq. miles

basin characteristics: rolling zone

Test flood = PMF (significant hazard + intermediate size)

using Corps of Engineers procedures;

Step 1 Determine peak inflow ( $Q_p$ ) from Guide Curves

from Guide curve for rolling terrain & d.a. = 4.5 sq. mi.  
Max. prob. flood = 1880 cfs / sq. mi.



## EFFECT OF SURCHARGE STORAGE (cont.)

then  $Q_p = 1880 \text{ cfs/sq. mi.} \times 4.5 \text{ sq. miles} = 8460 \text{ cfs}$

Step 2 Determine surcharge height to pass  $Q_p$ .

the crest of the dam (at elevation 103.0) is assumed to act as a broad-crested weir. Accordingly:

$$Q_c = CLH^{3/2}$$

for  $H < 1.5 b$   
 $b = 10' = \text{width of crest}$

where  $C = 3.09$

$L = \text{length of crest} = 650'$

$H = \text{head over crest}$

$Q_c = \text{discharge over crest elev. 103, cfs}$

the spillway (elev. 97.0) is assumed to act as a submerged sharp-crested weir. Accordingly:

$$Q_s = CLH_1^{3/2} \left[ 1 - \left( \frac{H_2}{H_1} \right)^{3/2} \right]^{0.385}$$

where  $L = 83.5'$


$C, H_1, \text{ \& } H_2$  as previously defined on p.3

$Q_s = \text{discharge over spillway elev. 97.0, cfs}$

then  $Q_{\text{TOTAL}} = Q_c + Q_s = Q_{\text{over crest}} + Q_{\text{over spillway}}$

Prepare stage-discharge table for different values of  $H = (\text{water elev.} - 103.0)$  for crest and corresponding  $H_1 = (\text{water elev.} - 97.0)$  for spillway.

Trial	w.s. elev.	$Q_c$ (cfs)	$Q_s$ (cfs)	$H_2$	$Q_{\text{TOTAL}}$ (cfs)
1	103.0	0	4600	0.2	4600
2	103.5	710	5190	0.6	5900
3	104.0	2010	5800	1.0	7810
4	104.5	3690	6400	1.5	10090



# EFFECT OF SURCHARGE STORAGE - (cont.)

## Step 2 (cont.)

from Figure 1 determine elev. required to pass  $Q_{p1} = 8460$  cfs

elev = 104.2 for  $Q_{p1} = 8460$  cfs

a. the surcharge height will be 7.2 ft. above spillway crest to pass  $Q_{p1}$ .

b. volume of surcharge storage ( $STOR_1$ ) in inches of runoff:

$$STOR_1 = \frac{\text{volume of surcharge storage} \times 12 \text{ in/ft.}}{\text{drainage area}}$$

$$= \frac{314 \text{ acres} \times (104.2' - 97.0') \times 12 \text{ in/ft.}}{4.5 \text{ sq. mi.} \times 640 \text{ acres/sq. mi.}}$$

$$STOR_1 = 9.42 \text{ inches of runoff}$$

a. compute  $Q_{p2} = Q_{p1} \left(1 - \frac{STOR_1}{19}\right)$

$$= 8460 \left(1 - \frac{9.42}{19}\right) = 4265 \text{ cfs}$$

$$Q_{p2} = 4265 \text{ cfs}$$

## Step 3

a. determine surcharge height and  $STOR_2$  to pass  $Q_{p2}$

surcharge height to pass  $Q_{p2} = 102.7$  (Figure 1)

$$STOR_2 = \frac{314 \text{ acres} \times (102.7' - 97.0') \times 12 \text{ in/ft.}}{4.5 \text{ sq. miles} \times 640 \text{ acres/sq. mile}} = 7.46 \text{ inches}$$

$$STOR_2 = 7.46 \text{ inches of runoff}$$

<b>HNTB</b> HOWARD NEEDLES TAMMEN & BERGENDOFF	Made by <u>H.M.</u>	Date <u>10/31/78</u>	Job No. <u>322-11-02</u>
	Checked by <u>PNB</u>	Date <u>11/6/78</u>	Sheet No. <u>7</u>
for <u>DEERING DAM</u>			

# EFFECT OF SURCHARGE STORAGE (Cont.)

## Step 3 (Cont.)

- b. Average  $STOR_1$  and  $STOR_2$  and determine average surcharge and resulting peak outflow  $Q_{P3}$

$$\text{Average } STOR = \frac{STOR_1 + STOR_2}{2}$$

$$= \frac{9.42' + 7.46'}{2} = 8.44 \text{ in'}$$

$$STOR_{Avg} = 8.44 \text{ inches}$$

$$c \quad Q_{P3} = Q_{P1} \times \left[ 1 - \frac{STOR_{Avg}}{19} \right] =$$

$$= 8,460 \text{ CFS} \times \left[ 1 - \frac{8.44}{19} \right] = 4,700 \text{ CFS}$$

STEP 4. A. Determine Surcharge Height for  $Q_{P3} = 4,700 \text{ CFS}$

From Fig. 1 El. = 103.0'

$$B \quad STOR_3 = \frac{314 \Delta c \times [103.0' - 97.0'] \times 12''/\text{FT}}{4.5 \text{ S.M.} \times 640 \text{ A/S.M.}} = 7.85''$$

$$c. \quad STOR_{Avg.} = \frac{8.44 + 7.85}{2} = 8.15''$$

$$D \quad Q_{P4} = 8,460 \text{ CFS} \times \left[ 1 - \frac{8.15''}{19''} \right] = 4,830 \text{ CFS}$$

STEP 5 A. Determine Surcharge Height for  $Q_{P4} = 4,830 \text{ CFS}$   
From Fig. 1 El. 103.15'

EFFECT OF SURCHARGE STORAGE

Step 5 (cont.)

$$B. \text{ } STOR_4 = \frac{314 A_c \times [103.15 - 97] \times 12''/\text{FT}}{4.5 \text{ S.F.} \times 640 \text{ A/SM}} = 8.05''$$

$$C. \text{ } STOR_{\text{AVG}} = \frac{8.15'' + 8.05''}{2} = 8.10''$$

$$D. \text{ } Q_{P_5} = 8,460 \text{ CFS} \times \left[ 1 - \frac{8.10''}{12''} \right] = 4,860 \text{ CFS}$$

EL. 103.15'

$$\text{ } STOR_5 = \frac{314 A_c \times [103.15' - 97'] \times 12''/\text{FT}}{4.5 \text{ S.F.} \times 640 \text{ A/SM}} = 8.05''$$

$$Q_{P_5} = 4,860 \text{ CFS}$$

OKOK


## CONCLUSIONS :

1. The test flood discharge ( $Q_{P_5} = 4,860 \text{ CFS}$ ) will overtop the crest by 0.15 feet.
2. The spillway (including stoplog sluiceway set at elev. = 97 FT) has the capacity of 4600 CFS
3. The spillway has the capacity to pass the 95% of the PMF.

DEE KING DAM

CALCULATION OF EATED CAPACITY @ elev. 97.0

Assume reservoir pool elev. = 97.0 what is capacity of stoplog sluiceway if gate completely opened.



critical depth will be passed as stoplogs are removed.

for rectangular channels of width  $b$

$$Q = 3.087 b H_e^{3/2}$$

reference: Std. Handbook for C.E., Merritt

where  $H_e$  = spec. energy head, datum = lip of channel  
assume negligible velocity head  $\therefore H_e = H$

$$\text{then } Q = 3.087 b H^{3/2} = 3.087 \times 5 \times 4.6^{3/2}$$

$$Q \approx 152 \text{ cfs, say } 150 \text{ cfs}$$

## ESTIMATING DOWNSTREAM DAM FAILURE HYDROGRAPHS

METHOD "RULE OF THUMB" IS USED TO ANALYZE THESE EFFECTS.

STEP 1: Determine or estimate Reservoir Storage (S) in A-F at time of Failure:

From data on Sheet 1:

Storage at Crest elevation = 4,984 AF

Plus Surge Storage:  $314A \times 0.57' = 179 "$

(S) = TOTAL STORAGE = 5,163 AF

STEP 2: Determine Peak Failure Outflow ( $Q_p$ )

$$Q_p = \frac{8}{27} \times \sqrt{g} \times W_b \times Y_o^{3/2}$$

$W_b$  = Breach width (Use 40% of total Length)  
 $= 0.40 \times 650' = 260'$

$Y_o$  = Total height from River bed to pool level at failure  
 = Hydraulic height  
 $= 25.6'$

$Q_p = 1.68 \times 260' \times [25.6']^{3/2} = 56,580 \text{ CFS. } \checkmark$

STEP 3: Prepare Stage-discharge curve for this section

REACH No. 1

REACH DATA:

$L = 3800'$

$S_o = 0.0126''$

$n = 0.080$

Approximate Location of Section ① Sta. 25+00 ±

CHANNEL DATA:

Shape: Trapezoidal (Approx.)

Bank Slope (L & R) = 9.2 : 1

Base Width = 200'

STEP 4: Determine the stage for ( $Q_p$ ) = 56,580 CFS from fig No. 2

a. Stage = 15.8' ± ,  $A = 5,460$  [IAF = 43,560 CFS]

Volume within the reach =  $3,800' \times 5,460' = 476 \text{ A-F}$

DEERING DAM - DISCATAGUOG RIVER

Since  $V_1 < S/2$  (The length of the reach selected is

$$\begin{aligned} b. \text{ Determine } Q_{P2(\text{TRIAL})} &= Q_P \left[ 1 - \frac{V_1}{S} \right] \\ &= 56,580 \times \left[ 1 - \frac{476 \text{ AF}}{5,163 \text{ AF}} \right] \\ &= 51,320 \text{ CFS} \end{aligned}$$

c. Compute Volume  $V_2$  using the stage provided by  $Q_{P2(\text{TRIAL})} = 51,320$  From figure No 2

$$\begin{aligned} \text{Stage} &= 15.1' \pm \\ \text{Area} &= 5,118 \text{ ft}^2 \\ V_2 &= \text{Length} \times \text{Area} = \frac{3,800' \times 5,118 \text{ ft}^2}{43,560} = 4 \end{aligned}$$

d Average  $V_1 \neq V_2$

$$V_{\text{AVG}} = \frac{V_1 + V_2}{2} = \frac{476 + 446}{2} \text{ AF} = 4$$

Compute final outflow =  $Q_{P2} = Q_{P1} \left[ 1 - \frac{V_1}{S} \right]$

$$Q_{P2} = 56,580 \text{ CFS} \times \left[ 1 - \frac{476 \text{ AF}}{5,163 \text{ AF}} \right] = 51,525 \text{ CFS}$$

REACH No 2

STEP 3: Prepare Stage - Discharge curve for section 2, see fig. 1.2

REACH DATA

CHANNEL DATA

Length (L) = 11,200' ±      Shape = Symmet 7  
Slope ( $S_0$ ) = 0.0067' (weir) Bank Slope 3:10:  
Manning's (n) = 0.08      Base width = 43'

Approximate location of Section ②: Sta: 61.



STEP 4: Determine the stage for  $Q_p = 51,525$  CFS from Reach No 1.

From fig No 2:

a. Stage = 12.75' ±      Area = 7,108' ±  
 $V_2 = \frac{11,200' \times 7,108' \pm}{43,560 \text{ CF/AF}} = 1,828 \text{ AF}$        $< S/2 = 2,581.5 \text{ AF}$   
 OK!

b. Compute  $Q_{p2(\text{trial})} = 51,525 \times \left[ 1 - \frac{1,828}{5,163} \right] = 33,286 \text{ CFS}$

c. From Fig No 2 determine the stage for  $Q_{p2} = 33,286$

Stage = 10.0' ±      → Area = 5,300' ±  
 $V_2 = \frac{11,200' \times 5,300' \pm}{43,560 \text{ CF/AF}} = 1,363 \text{ AF}$

d.  $V_{\text{Avg}} = \frac{1,828 + 1,363}{2} \text{ AF} = 1,595.5 \text{ AF}$

$Q_{p2} = 51,525 \times \left[ 1 - \frac{1,595.5}{5,163} \right] \text{ CFS} = 35,600 \text{ CFS}$

REACH No. 3

$Q_p = 35,600 \text{ CFS}$

STEP 3: Prepare Stage-Discharge Curve for section No. 3  
 See fig No. 2.

REACH DATA

Length = 3,000'  
 Slope = 0.033%  
 Manning's "n" = 0.08

CHANNEL DATA

Shape = Trapezoidal  
 Bank slopes Z = 6.9:1  
 Base width = 60'

Approximate Section Location ③ Sta: 163+00 ±

STEP 4: Determine the stage for  $Q_p = 35,600$  CFS.

From Fig. No 2

a. Stage = 14.9' Area = 2,426<sup>#</sup>

$$V_2 = \frac{3,000' \times 2,426^{\#}}{43,560 \text{ CF/AF}} = 167 \text{ AF} < 5/2 \quad \text{OK!}$$

b. Compute  $Q_{p2(\text{trial})} = 35,600 \times \left[1 - \frac{167}{5163}\right] \text{ CFS} =$   
 $= 34,450 \text{ CFS}$

c. Determine stage for  $Q_{p2(\text{trial})} = 34,450 \text{ CFS}$

Stage = 14.7' A = 2,373<sup>#</sup>

$$V_2 = \frac{3,000' \times 2,373^{\#}}{43,560 \text{ CF/AF}} = 163 \text{ AF}$$

d.  $V_{\text{avg}} = \frac{167 + 163}{2} \text{ AF} = 165'$

$$Q_{p2} = 35,600 \times \left[1 - \frac{165}{5163}\right] = 34,460 \text{ CFS}$$

REACH No 4

$$Q_p = 34,460 \text{ CFS}$$

STEP 3: Prepare Stage-Discharge curve for section No 4  
 See Fig. No 2.

#### REACH DATA

Length = 8,600'  
 Slope = 0.00285"  
 "n" = 0.06

#### CHANNEL DATA

Shape = Unsymmt. Trapez.  
 Bank Slopes:  
 $Z_{\text{LEFT}} = 7.4:1$   
 $Z_{\text{RIGHT}} = 15:1$   
 Base width = 430'

STEP 4 Determine the stage for  $Q_{P_1} = 34,460$  CFS.  
From Fig. No 2

a. Stage = 10.9' Area 6018<sup>sq</sup>  
 $V_2 = \frac{3,600' \times 6,018^{sq}}{43,560} = 1188 \text{ AF} < 5/2 \text{ OK!}$

b. Compute  $Q_{P_2(\text{TRIAL})} = 34,460 \left[ 1 - \frac{1188}{5163} \right]^2 =$   
 $= 26,530 \text{ CFS.}$

c. Determine stage for  $Q_{P_2(\text{TRIAL})} = 26,530$


Stage = 9.5' A = 5100<sup>sq</sup>  
 $V_2 = \frac{3,600' \times 5,100^{sq}}{43,560} = 1006 \text{ AF}$

d. Calculate  $V_{\text{AVG}} = \frac{1006 + 1188}{2} \text{ AF} = 1097 \text{ AF}$


$$Q_{P_2} = 34,460 \text{ CFS} \times \left[ 1 - \frac{1097}{5163} \right]^2 = 27,140 \text{ CFS.}$$

<b>HNTB</b> HOWARD NEEDLES TAMMEN & BERGENCOFF	Made by	LV	Date	2-22-5	Job No.	E-23-11-02
	Checked by		Date		Sheet No.	
NOTE: ELEVATIONS FOR ALL ELEVATIONS AND HYDROGRAPHS						

# ELEVATIONS (Feet Above M.S.L.)




# DEEZING DAM RIVER CHANNEL ANALYSIS




DISCHARGE (C.F.S.)

STAGE-DISCHARGE  
CURVES

FIG. 2





POSSIBLE TEST FLOOD  
DAMAGE AREA DUE TO  
DAM FAILURE

DEERING DAM

Deering Reservoir

NATIONAL PROGRAM OF INSPECTION OF NON FEDERAL DAMS	
DEERING DAM	
TEST FLOOD DAMAGE AREA	
Deering, New Hampshire USGS Quad. - Hillsboro, N.H.	Scale: 1:24,000 0 FEET 1000

APPENDIX E

INFORMATION AS CONTAINED IN  
THE NATIONAL INVENTORY OF DAMS



END

**FILMED**

8-85

# DTIC

panning map enj.  
Approximate loca

1374